

Architectural

Submission Template for Archicad 27 Architectural Native BIM Submission Template for Archicad 27 -

Publishing, reproduction, paraphrasing or translation without express prior written permission is strictly prohibited.

Trademarks

Archicad[®] is a registered trademark of GRAPHISOFT. All other trademarks are the properties of their respective holders.

> Credits Courtesy of GRAPHISOFT

--- Links last accessed: December 14, 2023 ---

If you have any comments, suggestions, or clarifications, please contact:

GRAPHISOFT Singapore 152 Beach Road #10-05 Gateway East Singapore 189721


mail@graphisoft.com.sg

Building and Construction Authority 52 Jurong Gateway Road, #11-01 Singapore 608550

Table of Contents

INTRODUCTION		•••••	•••••		•••••	5
GETTING STARTED						
THE ARCHICAD NAVIGAT	OR			••••••	•••••	9
STOREYS, PROJECT LOCA	TION AND	REFERI	ENCE	LEVELS	•••••	
SITE AND CONTEXT FROM						
DWG	••••••		•••••			
Surveyors' Data File	••••••		•••••			19
Point Clouds						
BIM SUBMISSION TOOLS	AND INTE	RFACE			••••••	
View Map Overview	•••••••		•••••			22
Quick Options	•••••••••••••••••					23
Favorites						24
Find & Select Criteria Set						
PREPARING THE FILE FOR	SUBMISS	ION		•••••		
3D Plan Views			•••••			
Creating/Modifying 3D l	Plan View <mark>s</mark>	- 3D Cu	itting	Planes		
Creating/Modifying 3D I	<mark>Plan V</mark> iew <mark>s</mark>	- Filter	and C	ut Elements	in 3D	
ACCESSIBILITY & VENTILA						
Accessibility Routes			•••••			
Accessible Doors	•••••••••••••••••		•••••			
Clearance Boxes			•••••			
Zone Accessibility	•••••••		•••••			
Modes of Ventilation						
Lifts						
Toilets and Toilet Comp	artments .		•••••			
Accessibility Objects						47
SCHEDULES				••••••		
Accessible (Audience) Se						
Hearing Enhancement S	bystems					50
Parking Lots						
Accessible/Elderly Frien	<mark>dly</mark> Rooms	(Hospit	ality l	Projects Only	/)	54
All Rooms						56
Stairs						57
Shelters						
AREA TABULATION			•••••	••••••	•••••	61
GFA	••••••		•••••			61
STRATA						
SGFA						
COVER PAGE						
A&A WORKS (RENOVATIO						
COLLISION DETECTION (C						
MERGING THE TEMPLATE						
Favorites						
Attributes						
Project Info	••••••	•••••	•••••	••••••		73

Views, Layouts and Master Layouts	73
Publisher Sets	
Renovation Filters	
Model View Options	
Graphic Override Combinations	
SUBMISSION REQUIREMENTS	
Final Check	
File Formats	
ACKNOWLEDGEMENT	



INTRODUCTION

The objective of this document is to assist qualified persons (QPs) in developing BIM models to meet the new requirements of the Building Information Model (BIM) submission (Native BIM Submission).

The document describes the features of the Architectural Native BIM Submission Template for Archicad 27 and provides a step-by-step guide to apply them in projects. The template creates a basic structure to assist the QPs in preparing the BIM models for regulatory approval according to the Architectural BIM e-Submission Guideline. It is by no means an exhaustive template and QPs are allowed/required to edit/change it accordingly to suit their needs.

For any additional requirements that require customizations to a certain extent, QPs are also advised to make reference to the training materials distributed or to consult the respective software vendor for any enquiries on the application.

If there are contradictions between this submission guideline and vendor's instructions, BCA BIM team shall be contacted for clarification. Please note that any BIM Submission Guidelines and templates shall be collected from the BCA BIM team.

This material is to serve as a reference for GRAPHISOFT Archicad 27 users only.

Find the BIM e-Submission Templates and Guidelines at the CORENET website here: https://www.corenet.gov.sg/general/building-information-modeling-(bim)-esubmission.aspx

Find the Archicad Libraries for each template on the GRAPHISOFT SG website here: (Requires GRAPHISOFT ID and SSA license to log in) https://graphisoft.com/sg/ssa/downloads

GETTING STARTED

Once you have downloaded the template from the CORENET website, do the following preparations before using the template for the first time.

- Place the sg_arch-submission-template_v27.tpl file to: Option 1: On your file server in a dedicated template folder. Then in Archicad 27 New dialogue, use "Browse" and load this template. If the path or name changes, then you'll need to browse again to load this template again. Option 2: Copy the template to the Archicad application folder, the template will auto load into the New dialogue when you start the application. This folder is usually located at C:/Program Files/GRAPHISOFT/ARCHICAD 27/Defaults/ARCHICAD.
- 2 Place both the GSSG ARCH Library.lcf and GSSG General Library.lcf library container files into a folder where they will not be modified/moved/deleted, such as a company file server. There are following sections that will go into this in more detail.
- 3 Launch GRAPHISOFT Archicad 27 using the desktop shortcuts.



- 4 The Start Archicad 27 dialog appears, choose New... at the top of the dialog.
- 5 Click into the dropdown list and use the **Browse Template...** option to locate the **sg_arch_submission-template_v27.tpl** template file.
- 6 Choose the Architectural Profile 27 Work Environment and click New.

Templat	ew Project fro					
		ion-template_v2	7.tpl		~	
🔵 Latest F	roject Settings					
	vill create a new	Project based on	a selected t	templa	ite	
file.	vill create a new a new instance o onment Profile	-	a selected t	templa	ite	
file.	a new instance o	f Archicad	a selected t	templa	v.	


Note 1: To ensure the authenticity of the downloaded template file, make sure you obtain it from the CORENET BIM Support Team at:

https://corenet.gov.sg/general/building-information-modeling-(bim)-e-submission.aspx

Note 2: The template is constantly improved based on user feedback, therefore minor differences may occur between the actual version and the screenshots presented in this guide. Only the latest versions of the template are available on CORENET.


The naming of the template file indicates the updates and revisions, such as ...template_v27.tpl for the initial version, then ...template_v27.1.tpl, ...template_v27.2.tpl, etc., if available subsequently.

7 Once Archicad 27 is launched, it will not prompt for missing libraries as all warnings are collated into the Action Center, therefore go to File/Libraries and Objects/Library Manager... to check if both the GSSG ARCH Library.lcf and GSSG General Library.lcf are linked to the project. If not, then you need to Add them.



- 8 Click Add.... Locate the LCF file and click Open.
- 9 Click **OK** to close the Library Manager and load the libraries.

THE ARCHICAD NAVIGATOR




The Navigator palette is displayed on the right side of the interface, containing the following tabs/selectors:

• **Project Map** - the entire model structure and the different viewpoints of the project.

	=•
Search Project Map	
✓ △ -> File/Info/Project Info ✓ ▲ Stories	^
10. ROOF STOREY	
8. 9TH STOREY	

• View Map - model views filtered for different purposes. The folder structure here is organized for the native BIM submission.



 Layout Book – some predefined layouts and master layouts are included in the Template, such as the required Cover Page which lists Views, Drawings and Schedules in the Project. All 2D Views and Schedules should be added to Layouts for submission.


For CP83 submission or project phases after the submission you may still want traditional 2D format deliverables. The title blocks can be edited from the **Masters** section, and can be customized for the different authorities and departments if not submitting a native Archicad file.

Search Layout Book
✓ 🕞 -> File/Info/Project Info
✓ COVER PAGE
BCA_BP_ DRAWING LIST

Note 1: Avoid changing other parts of the master layout unless you are sure that the AutoText fields (fields containing # marks) are kept intact, otherwise some texts might not appear correctly on the final layouts.

Note 2: Updating the master layouts is a one-time procedure. To update the original template use **File/Save as...** menu option and override the existing template file using **Archicad Project Template (*.tpl) file** type setting. From now on the new template file can be used for new projects.

• **Publisher Sets** - collection of items referring to elements of the View Map and the Layout Book set for simplified and repeated document output. The most necessary formats are set as guidance and new publisher sets can be created with combined formats within the same publisher set.



The BIM submission template serves as a basic platform to help you in preparing your model for regulatory approval. Submitting native files is not mandatory and you are free to submit your projects in the traditional way and edit the template according to your needs as long as the final results presented to the authorities meet the requirements specified in the Code of Practice for BIM Submission documents.

Note: Traditional submission formats are still accepted, but not supported or recommended by BCA, nor GRAPHISOFT Singapore as the creator of this template, from July 2016 onwards.

STOREYS, PROJECT LOCATION AND REFERENCE LEVELS

By default, the template contains 10 generic storeys, a roof and foundations. To edit the Story Settings to go the **Design/Story Settings...** menu.

All generic storeys have a consistent floor-to-floor height of 3500 mm, which can be edited for the requirements of the specific projects. Major changes in the story settings, such as the number of storeys and heights should be carried out before starting the project.

1 If your project has less storeys than in the template, select the unwanted storeys and click **Delete Story**. If you want to add storeys select an existing story and use the **Insert Above/Insert Below** buttons respectively.

No. Name	Elevation	Height to Next	<u>• •</u>	
9 10TH STOREY	31500	3500		1
8 9TH STOREY	28000	3500	\checkmark	ł
7 8TH STOREY	24500	3500	\checkmark	
6 7TH STOREY	21000	3500	\checkmark	
• 5 6TH STOREY	17500	3500	\checkmark	
4 5TH STOREY	14000	3500	\checkmark	
3 4TH STOREY	10500	3500	\checkmark	
2 3RD STOREY	7000	3500	\checkmark	
1 2ND STOREY	3500	3500	\checkmark	
0 1ST STOREY	0	3500		
-1 BASEMENT 1	-1000	1000		1
Insert Above Insert Below	Delete Story			

Find more information on the Story Settings on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F140_UserInterfaceD ialogBoxes%2F140_UserInterfaceDialogBoxes-33.htm The current template uses the *Singapore Height Datum* as the height reference when displaying manually placed elevation dimensions using the Dimension tool, meaning that all elevation heights will be measured from -5913.

Section and Elevation story levels are referenced to the *Sea Level*, by default showing an altitude of -5.913 for Project Zero. Altitude (AMSL, or Sea Level) is set for a default of +5.913 meters for Singapore. To change the sea level reference:

1 Go to **Options/Project Preferences/Location Settings...** and change the **Altitude (Sea Level)** value (also change Time Zone (UTC) if settings differ from Singapore time zone).

Project Name:	-> File/Info/Project Info Edit
Site Full Address:	Address 000000 SINGAPORE Edit
Latitude:	1° 21' 3.7098* N ~
Longitude:	103° 51' 7.5687" E ~
Time Zone (UTC):	(UTC+08:00) Kualumpur, Singapore 🗸
Altitude (Sea Level):	5.91 🕨 m
	Show in Google Maps
₼	
SURVEY POINT	
Symbol Type:	
Symbol Type:	$\rightarrow \oplus \oplus$
Symbol Type:	
Symbol Type:	-30090429 27015613
Symbol Type:	-37015613
Symbol Type:	-37015613 -5913
Symbol Type:	-37015613 -5913
Symbol Type:	-37015613 -5913 SS FOR IFC
Symbol Type: Posmon Easting Northing Elevation GEOREFERENCING PARAMETER Projected CRS Name	-37015613 -5913 ss FoR IFC Tranverse Mercator
Symbol Type: Posmon Easting Northing Elevation GEOREFERENCING PARAMETER Projected CRS Name Description	-37015613 -5913 25 FOR IFC Tranverse Mercator SVY21 is a geodetic coordinate datum based on the V
Symbol Type: Posmon Easting Northing Elevation GEOREFERENCING PARAMETER Projected CRS Name Description Geodetic Datum	-37015613 -5913 ts FOR IFC Tranverse Mercator SVY21 is a geodetic coordinate datum based on the V SVY21

2 Additionally, you can also set Project North either by typing the value or simply clicking on the symbol and rotating it within the dialog.

Find more information on **Project Location and Project North** settings on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F020_Configuration %2F020_Configuration-34.htm

Depending on the project, you may want to edit the existing project reference levels.

1 Go to **Options/Project Preferences/Reference Levels...** dialog and change the values of the **2nd Reference Level**. The units of the values follow the working unit settings, millimeters by default. The 1st Reference Level has been altered to display *Singapore Height DATUM* By choosing, under Relative to, then when placing your elevation dimensions, level dimensions or adding height value inputs for mesh points, the exact values provided by the land surveyors.

Reference Levels	Elevation	Relative to	
Project Zero	0	$\overline{\nabla}$	
a 1st Reference Level	0		
🚊 ² Singapore Height Datum	-5913		
🚊 _ Sea Level	-5913		

Find more information on the **Reference Levels** on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F140_UserInterfaceD ialogBoxes%2F140_UserInterfaceDialogBoxes-28.htm 3 To apply the new reference level, select the Sections or Elevations you want to be modified from the Project map, right-click and in the context menu and choose Selection/Elevation Settings. On the Story Levels Symbol and Text panel choose the Reference Level (by default Sea Level).

▼ E STORY LEVELS SYMBOL AND TEX	π
🔹 🕨 📑 🕁 Story Marker Geom	netry
Show Marker Head	Reference Level
Fills and Colors	1st Reference Level \checkmark
Air Space	Story Name Placement Abc
0. Abc +1, 000 300 • 2762 • 24	100 0.00° 100 100

4 When adding Elevation Dimensions to the Sections/Elevations with the new elevation reference, adjust the Elevation Dimension settings as well to the new reference level.

Dimension Default Settings	? ×
公 ·	Default
▼ K UIMENSION TYPE	
Dimension Type: I ← I ← I ← I ← I ← I ← I ← I ← I ← I ←	Dimension Origin: Singapore Height Datum ~ Static Dimension
$4^{2} \rightarrow \checkmark \checkmark \checkmark \checkmark \checkmark \checkmark$ Witness Line:	 ✓ 45 ↓ 85

SITE AND CONTEXT FROM EXTERNAL CONTENT

Context to the site can be imported and created from many different formats, such as 2D DWGs, tabulated text files (XYZ coordinates) or Point Clouds.

DWG

There are two main methods to link DWG files into Archicad. For both methods, it is advised to create a new **Independent Worksheet**, and use the **Trace and Reference** functionality to view the DWG from the Worksheet on the relevant floor plan.

- 1 Place Drawing Use the Drawing Tool, to add into a Worksheet. Make sure to set the Drawing Units when prompted and check any linked images/SHX (fonts) files. Once placed, within the Drawing Tool, the DWG Embedded Layers can be turned on/off as needed. The Drawing can be exploded and the 2D content embedded by using right-click, Explode into Current View.
- 2 Attach Xref From the File/External Content/Attach Xref dialog. Set to Drawing's own origin, check the Translator being used before attaching, and any linked images/SHX (fonts) files when prompted. Place the DWG in the correct location and choose which Layers you wish to import. These imported Layers will be available in the projects Layer Settings, separated after all other Layers. If the Xref will be deleted from the Project, these separated Layers will also be removed as well.

To accommodate the extents of the DWG and site boundary, Section and Elevation markers may need to be adjusted on the floor plan. To create the 3D terrain from the 2D DWG:

- 1 Use the Mesh Tool from the Toolbox, to trace the boundaries of the terrain.
- 2 To trace the continuous ridge lines, select the **Mesh** in the plan, and activating the **Mesh Tool** in the Toolbox.
- 3 Activate the Magic Wand, by holding the SPACEBAR and click on the ridges of the DWG reference.

Keep Fit to User Ridges selected in the appearing dialog and click OK. Create the remaining ridges in the same way.

🔼 New Mesh Points	?	×
Add New Points		
O Create Hole		
Fit to User Ridges		~
Cancel	OK	

4 After tracing all the ridges, make sure that the Mesh is selected, and the Mesh Tool is still activated. Click on a **node** of a ridge line and from the pet palette choose the **Elevate Mesh Point...** command. Check the **Apply to All** checkbox to raise all nodes of the clicked ridge and choose the appropriate reference plane, for example the False Datum. This way you can enter the same values as on the surveyor's plan. Elevate the remaining ridges in the same way.

Height: 5913 to Singapore Height Datum Mesh Reference Plane Project Zero	5913 to Singapore Height Datum Mesh Reference Plane	Mesh Point Height ?	×	
to Singapore Height Datum Mesh Reference Plane Project Zero	to Singapore Height Datum Mesh Reference Plane Project Zero 1st Reference Level	Height:		
Apply to All Project Zero C C C C C C C C C C C C C	Apply to All Project Zero 1st Reference Level	5913		
	1st Reference Level	to Singapore Height D	Datum 🕨 Mesh Reference Plane	\leftrightarrow
		Apply to All		

5 As a last step adjust the corner nodes of the Mesh (**uncheck Apply to All**) manually in 3D or 2D.

In case the imported topography only contains spot points, and not ridges, you can still add and elevate the points as follows:

1 Select the **Mesh** and **activate the Mesh Tool**. Set the Geometry Method in the InfoBox to **Polygonal geometry method**. Note that other Geometry Methods will not be able to create spot points.

Default Settings	• 🔄 🖓 🖗 🚳 🗖 • 🚺 soil
▶ 88 [0. 1st STOREY]	X [] [3D / All]

- 2 Double-click the referenced surveyor points to create a spot point. Click OK with the Fit to User Ridges option selected in the appearing dialog. Create the remaining points in the same way.
- 3 Elevate the points one-by-one using the Elevate Mesh Point... command (similarly to the ridges).

Surveyors' Data File

The surveyor can also provide a topographic file in TXT or XYZ format which will be easier to import into Archicad, without the need to Trace over the original.

- 1 Go to File/Interoperability/Place Mesh from Surveyors Data....
- 2 Select the surveyor data file and click **Open**, a dialog will pop up for configuration settings for placement and altitude. Set the altitude according to the Project Location settings.

Place Mesh from Surveyors Dat	a	?		×	
Surveyors Unit:	meter			~	
Placement:					
Define graphically					
Original location					
Zoom to the new mesh					
Project Zero is above Sea Level by:					
	0.00	meter			
	Cancel		ОК		

3 Click **OK** and **click** into the model to place the resulting generated Mesh.

Note: The topographic files of both TXT and XYZ format must be saved with ANSI encoding prior importing them into Archicad to be shown in the model space.

Point Clouds

Archicad natively supports the industry standard E57 and XYZ point cloud file formats which can be imported and used to model existing buildings before renovations, surroundings or asbuilt structures.

- 1 Open File/Interoperability/Import Point Clouds... from a floor plan viewpoint.
- 2 Select the point cloud file and click **Open**. In the case of XYZ format, the **Format Conversion** dialog will appear.
- 3 In case of E57 format, the **Create Point Cloud Objects** dialog will appear, you need to specify the name of the object the point cloud will be converted to and the location of the generated library.


LCF files will be gener added to the Linked L	rated from every imported P Library.	oint Cloud and automati	cally
Generate LCF files in t	this folder:		
C:\Users\GSSG-crive	ral\Documents\GRAPHISOFT	Point Clouds Bro	wse
Point Cloud names:		Convert	ed files: 1
Source Name	Object Name	LCF File Name	
GSSG sample.e57	GSSG sample	GSSG sample.lcf	^
			~
Point Cloud Ob automatically re	jects and LCF files sharing th enamed.	e same name and locati	on will be

4 Click Create and Place.

5 The **Place Point Clouds** dialog will prompt for the placement location of the generated object. Set the position and click **OK**, the object will be placed into the floor plan selected.

	?	\times
lly		
0. 1st STOREY		~
Cancel	ОК	
		Illy 0. 1st STOREY

Note: The recommended use of imported point clouds is for referencing only, these objects cannot be used for visualizations.



Find more information on **Importing Point Clouds** on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F120_Interoperabilit y%2F120_Interoperability-32.htm

BIM SUBMISSION TOOLS AND INTERFACE

View Map Overview

The Navigator - View Map contains predefined views, which can be used as-is for the submission:


- The DEFAULTS folder contains views to help the QPs with modeling, by storing default settings in which all elements are visible and editable 3D views for generic references and the WORKING VIEWS folder, a Cloned Folder of the Stories viewpoints of the Project Map for both architectural and structural modeling.
- The BCA/BP folder contains folders and views that the officers will check upon submission. The folder contains both 2D and 3D views. The 2D PLANS folder is to be checked primarily, while views in 3D PLANS will be used for the same purpose and to clarify issues, which are not visible from the 2D plans. The latter might need manual adjustments, depending on the project design and the level/slab positions.
- The views in the SCHEDULES folder will also be checked by the officers to ensure that the model complies with the regulations. The QPs can use them for data input as well.
- The COVER PAGE folder is purely to collect views that are part of the submission cover page.

Search View Map					
✓					
> Defaults					
> 🛅 BCA					
> 🛅 FSSD					
> 🛅 URA					
> 🛅 LTA					
> 🛅 NPARKS					
> 🛅 РОВ					
> 🚞 NEA					
> 🚞 SCHEDULES					
> 🗋 COVER PAGE					

Quick Options

During modelling and working in the project, switching to a pre-defined View can modify what is visible on the screen. To avoid modifying these Views, at any time you can switch the settings on the **Quick Options Bar** at the bottom of the working window, for example switch the Layer Combination to *All Visible Shown Editable* – or switch to any of the DEFAULTS in the View Map.

Changing these **Quick Options** will not affect the stored View, to revert back to a stored View, just double-click the item in the View Map.



When working with Schedules the Quick Options bar is not visible, but all schedules are still editable. As an alternative, you can show the Quick Options palette by Window/Palettes/Quick Options menu command. This palette can also be used on other viewpoints, instead of the Quick Options bar.

Favorites

The template contains many predefined favorites for the QPs' convenience. These can be easily accessed by hovering on a Tool in the Toolbox and clicking on the appearing arrow. Alternatively, in the InfoBox, in the Main panel, click the arrow next to the Tool Settings button.

	lit View Desig			tions '	Teamwork	Wind	ow Hel
\mathbf{D}	y 🕺 🎢 🎢	•		K XY: ▼	# •	€ ₿	-
Main:			Layer:				Geomet
Default S	iettings		• A-	_WALL	E-	•	
	88 🖺 [0. 1ST	STOREY]				×	<u> </u> [Ad
Design							
\square	Q Search Favor	rites					4 £
Π	🚖 Favorites					~	ŕ_
	\frown			\frown			
\sim							
$\langle \! \rangle$							
\Diamond							

- Arch favorites items under this has BIM SUBMISSION folder containing the Favorites needed specifically for submission and free floating Favorites which are generic.
- **Defaults** contain Favorites from the standard Archicad template and the defaults for each element. These can be deleted if need be.
- STRUCTURAL ELEMENTS are used in case structural elements will be used when working together with the structural teams in an integrated model workflow.

To ensure that the information stored in a Favorites applies the desired information to elements, check the Element Transfer Settings. This allows to choose which settings are applied, either when using Favorites or using Pick Up and Inject.

To adjust which transfer setting is used when double-clicking a Favorite to apply, go to **Window/Palettes/Favorites**, click the **cogwheel** on the top right of the palette and choose **Element Transfer Settings...** or access the dialog via **Edit/Element Settings/Element Transfer Settings**.

The left side are presets, the row with a star icon and tick represents the default for Favorites. To change, select a preset and click into this column, to make sure that the star icon appears next to Transfer All Settings (excl. Home Story) [FOR FAVORITES].

Q Search Transfer Sets		Name:	Editable
Name 🔺 🖄	~	Transfer All Settings (excl. Home Story) [FOR FAVORITES]	-0-
Exclude ID / Layer		Optional Settings to Include during Transfer:	203
Exclude Label Text		Q Search Transfer Sets	
Exclude Library Part Exclude Metadata Exclude Size / Height / Elevation Stair 2D Symbol Stair Geometry Stair Structure / Finish Transfer All Settings Transfer All Settings (excl. Home Story) [FOR FAV 🐼 Transfer Structure / Display / Library Part		 > ✓ A^Q Angle Dimension > → Beam > ✓ Seam > ✓ Seable Carrier Branch > ✓ Seable Carrier Fitting > ✓ Cable Carrier Routing > ✓ Cable Carrier Routing > ✓ Change Marker > □ ① Column > □ ⑪ Curtain Wall > ✓ ⊕ Detail/Worksheet 	
New Delete		Cancel	ОК

Find more details on the Element Transfer Settings

on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F030_Interaction%2F 030_Interaction-99.htm

Find & Select Criteria Sets

To quickly select elements with specific criterion, use the **My Criteria Sets** in Find & Select, access by **Edit/Find & Select** or **CTRL+F**.

Find & Select		×
Criteria Set Name:	Accessibility - Clearance Boxes	 ▶
	Built-in Criteria Sets	
Criteria	All Elements	
Element Type	All 2D Elements	
Layer	All 3D Elements	
	All elements on unlocked and visible layers	
	Inverted elements	
	Invalid Stairs	
	My Criteria Sets	
	Accessibility - Clearance Boxes	
	Accessibility - Routes	
	Accessibility - Symbols	
	Accessibility - Zones	
	All Elements	
	All MEP Elements	
	All Modeling Elements	~
Add 💌	BScore - by Descriptions	<i>T</i>
Add	BScore - Undefined	
	Details - Air Space CFills	
Selected:	Details - Anotations	
Editable:	Details - Background CFills	
	Details - Non-BMat Fills	
	Layers Archi	
	Layers Landscape	
	Layers MEP	
	Layers STR	
	Position - Exterior	
	Position - Interior	
	Position - Undefined	
	Structural - Load Bearing	
	Structural - Non Load Bearing	
	Structural - Undefined	
	Zone MOV - Mechanical	
	Zone MOV - Mechanical and AC	
	Zone MOV - Natural	
	Zone MOV - Natural and AC	
	Zone MOV - Undefined	


When opening the element settings from the whole selection, by using CTRL+T, only the settings of the last selected element type will be visible and editable. To change the settings of a different element, double-click that Tools icon in the Toolbox. To edit some details of the entire selection, like Layer and Properties, go to Edit/Element Settings/Edit Selection Set...

PREPARING THE FILE FOR SUBMISSION

3D Plan Views (Optional)

As part of the preparation process the QPs need to set and refine the **3D Plan** views of the different stories. Since the Slab positioning and levels may vary significantly there is a high chance that some manual adjustments are needed to the preset 3D views.

The preset 3D Plan views use the 3D Cutaway function to limit the vertical range of the 3D view. Once the view is opened from the View Map, you can adjust the **Cutaway plane** by clicking on it and dragging it or simply switch to the **Project Map** in the Navigator and open a section/elevation to see the plane. If needed, click on the purple line and drag it to the desired height to modify which stories are visible.



Creating/Modifying 3D Plan Views - 3D Cutting Planes

- 1 Open any of the views in the BCA/BP/3D PLANS folder in the View Map.
- 2 Use the **3D Cutaway** function of the Standard Toolbar to set the cutting planes.



- 3 After adjusting, click **Finalize**.
- 4 From the View Map, save the View using the Save Current View... button at the bottom of the Navigator.

ration of the second se	e ⊕	:=	×	1
	-	_	_	

5 To change an existing view, right-click on the view you'd like to modify and choose Redefine with Current Window Settings from the context menu.

Open	
New Folder	
Rename	
Redefine with Current Window Settings	
× Delete	

Note: When changing story heights (Design/Story Settings...) the elevation of Cutaway Planes must be readjusted manually.

Find more details on the 3D Cutting Planes on the Archicad 27 Help here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F050_ViewsVB%2F05 0_ViewsVB-23.htm Creating/Modifying 3D Plan Views - Filter and Cut Elements in 3D

- 1 Open any of the views of the BCA/BP/3D PLANS folder in the View Map.
- 2 Turn off the 3D Cutaway, to show the full 3D model.



3 Right-click the 3D Window Tab of the opened view and choose Filter and Cut Elements in 3D....

[] [3D / All]	Recent Related Views	
	Save as View	- 11
1	Pick Up View Settings	- 11
	Get Last Settings	- 11
	Match All to Current	
G	3D Styles	•
Į,	3D <u>P</u> rojection Settings Ctrl+Sl	hift+F3
	Set Window Size	
	Perspective SI	hift+F3
6	Axonometry (Ctrl+F3
C	3D <u>C</u> utaway	Ctrl+Y
3	Filter and Cut <u>E</u> lements in 3D Ctrl+	+Alt+A
	Close Tab 3D / All	

4 Set Stories to Show in 3D to Limited and adjust both the To and From controls to the range you want visible in 3D and click OK.

Filter and Cut Elements in 3D		?	×
Stories to Show in 3D			
○ Infinite			
Limited:			
То	0. 1ST STOREY		~
From	0. 1ST STOREY		~
Trim Elements to Story ra	inge		

5 From the View Map, save the View using the Save Current View... button at the bottom of the Navigator.



6 To change an existing view, right-click on the view you'd like to modify and choose **Redefine with Current Window Settings** from the context menu.

-	Ор	en						
			lder					
		nam						_
	Red	defir	ne with	Currer	nt Wind	low Se	ettings	
×	De	lete						

ACCESSIBILITY & VENTILATION

Accessibility and Modes of Ventilation has to be marked by adding accessibility routes, clearance boxes, accessibility objects (symbols) and by setting the properties of zones regarding both. This part summarizes ventilation and accessibility in general, the use of the accessibility related objects will be introduced in later parts of this document.

Accessibility Routes

Accessibility routing uses the Wall tool.

1 To place, use the Wall Favorite, Accessibility Route (1200/100), under the BIM SUBMISSION/Accessibility Symbols/Objects folder.

\square	Wall	Search Favorites	र ्ट्रि •
Ū	Column	Accessibility Symbols/Objects	Ł
\square	Beam		
\bigotimes	Slab		
\bigtriangledown	Roof	Accessibility Route Accessibility Route Accessibility Route (1200/100) (1500/100) (1800/100)	
\triangleleft	Shell		
B	Stair		
FF1	Railing		
Ħ	Curtain Wall		

- 2 **Double-click the preview** to activate the Wall tool and apply the Favorite settings. Check the following **Classification and Properties** settings:
 - Element Classification = (Unclassified)
 - ID = (according to company naming standards)
 - Structural Function = Undefined
 - Layer = Accessibility Route.BCA_BP

• 🖹 C	LASSIFICATION AND PROPERT	IES	
	CLASSIFICATIONS		^
	ARCHICAD Classification - v 2.0	0 (Unclassified)	
	MEP Submission Classification	(Unclassified)	~
•	ID AND CATEGORIES		^
	ID	ACCR_004	
	Structural Function	Undefined	
	Position	Interior	
•	RENOVATION		

3 Create the Wall using the Chained geometry method. When reaching doors, make sure the route is not intersecting with the frames or leaves.


Default Settings	O - Accession	bility Route.BCA_B	P 🕨		<u>F</u>

Note: The Bottom offset of the wall is set to 0 by default. Always make sure that the accessibility route is positioned on the top surface of the actual Slabs to avoid clashes.

Accessible Doors

Accessible doors have to be placed where access to an accessible zone/room is required. The only difference between regular and accessible doors is that the latter have their minimal spaces defined and shown automatically on accessibility related plan views.

1 To place, use any of the **Door** Favorites starting with **Accessible** under the **BIM SUBMISSION/Doors** folder.



2 **Double-click the preview** to activate the Door tool and apply the Favorite settings.

Check the following settings:


- Minimum space requirements, for double doors only one door needs to be accessible
- Under Classification and Properties panel, Accessible = True
- 3 Place the Accessible Doors into the relevant Walls.

Note: To insert a regular door, use the Favorites from the same folder without the 'Accessible' prefix.

Clearance Boxes

Clearance boxes are only to be placed for accessible doors which have their minimal spaces defined and shown.

1 Use the Object Favorite Clearance Box (1200x1200/2200) under the BIM SUBMISSION/Accessibility Symbols/Objects folder.



2 **Double-click the preview** to activate the Object tool and apply the Favorite settings.


Check the following Geometry settings:

- Bottom offset is level with the Slab top surface
- Box height is in accordance with the Door height

Check the following Classification and Properties settings:

- Element Classification = Building Element Proxy
- ID = (according to company naming standards)
- Structural Function = Non-Load-Bearing Element
- Accessible = True
- Layer = Clearance Boxes.BCA_BP

Place the box object using the **Rotated Diagonal geometry method**, to easily snap to the corner points of the Door 2D minimal space (even for non-orthogonal elements).



Note: The final clearance has to show both the 2D (solid color fill) and 3D clearance (dashed fill in 2D, box in 3D).

Zone Accessibility

Accessibility of Zones needs to be set if the accessibility route goes through the zone or is reaching it via an accessible opening.

1 Open the Zone settings Classification and Properties panel and set the Accessible (spaces and elements) property value to True under ARCH | REGULATORY REQUIREMENTS.

	CLASSIFICATIONS	
\checkmark	ARCHICAD Classification - v 2.0	Space
	Descustion Status	
	Renovation Status Show On Renovation Filter	New
	ARCH REGULATORY REQUIRE	
·	Accessible (spaces and elemen.	
5	Mode of Ventilation	Mechanical
5	Accessible Room (hospitality o	· True
e	Elderly Friendly (hospitality only)) False
	ARCH SHELTERS	
ര	Dwelling Unit Type (shelter zon	Undefined
e	GFA of Unit (sqm) /to be adde	
ര	Nominal Occupancy /to be ad	
—		-

Note 1: Zone Favorites include stored information about accessibility.

Note 2: Zones can only be placed using boundary construction methods if the *Renovation Statuses* of those match the Zones. For example, if the bounding Walls' Renovation status is *New*, only a *New* Zone can be auto placed inside. Therefore, check the Renovation palette (Window/Palettes/Renovation) of both the bounding Walls and the Zone being placed.

Renovation	×
Selected Elements:	
표 & ፲	ŕÞ
Renovation Filter:	
00 Show All Elements	~


As an alternative data input method, you can also use Schedules once the Zones are placed but their accessibility has not been defined yet.


- 1 Open the BCA_BP_ROOMS (All) Schedule from the Project Map or View Map.
- 2 **Click into any of the checkboxes** of the **Accessible** column to change the accessibility of the Zones.

Mode of Ventilation	_	Accessible	Hotels, guesthouses, dormitories, etc.		
	Area	(space)	Accessible Room	Elderly Friendly Room	
Mechanical and Air-Conditioned	14.38	\square			
Mechanical	24.64				
Mechanical	29.85				
Mechanical	30.98				
Mechanical	36.86	\boxtimes			
Mechanical	62.78				
Mechanical	104.97				
Mechanical and Air-Conditioned	15.06				
Natural	14.46	\boxtimes			
Natural	15.07				
Natural and Air-Conditioned	16.63				
	365.68 m ²				


Note 1: Accessible Room and Elderly Friendly Room checkboxes refer to hospitality spaces only, where the room provides better accessibility and more space.

Note 2: The default accessibility property value is *False* therefore non-accessible Zones do not need to be modified.





Courtesy of P&T Consultants Pte Ltd.



Modes of Ventilation


Setting the Mode of Ventilation for Zones follows the same method as accessibility described above, through either:

Zone Settings: Open the Zone settings Classification and Properties panel and set the Mode of Ventilation property value to the required one under ARCH | REGULATORY REQUIREMENTS.


or

Schedule: Open the BCA_BP_ROOMS (All) Schedule and click into any of the cells of the Mode of Ventilation column, then choose a value from the option list.

Note: The default Mode of Ventilation property value is *Mechanical*.



Courtesy of P&T Consultants Pte Ltd.




Courtesy of P&T Consultants Pte Ltd.

Lifts

Accessible lifts have to be set according to the accessibility code and will be highlighted on plans. For actual requirements please refer to the relevant codes.

1 Use the **Object** Favorite Lift Car or Accessible Lift Car under the BIM SUBMISSION/Lifts folder. Choose a version based on the required graphical appearance on plans (Symbolic 1/Symbolic 2/Scale Sensitive).



Note: The stored Favorites include the lift shaft set at a minimum thickness of 1mm. This is only necessary to make the lifts visible in their full heights when highlighted for accessibility. Actual shafts are to be built using the Wall tool and an additional Empty opening (Door tool) placed.


Double-click the preview to activate the Object tool and apply the Favorite settings.

Check the following Classification and Properties settings:

- Element Classification = Elevator
- ID = (according to company naming standards)
- Structural Function = Non-Load-Bearing Element
- Accessible = False or True (as needed)
- Layer = A-_LIFT---_E-
- 2 Place the necessary lifts.

Add the 2D symbol for accessibility to mark the elevators on plans as well.


1 Use the **Object** Favorite **Symbol of Access** under the **BIM SUBMISSION/Accessibility Symbols/Objects** folder



2 **Double-click the preview** to activate the Object tool and apply the Favorite settings.


Check the following Classification and Properties settings:

- Element Classification = Building Element Proxy
- ID = (according to company naming standards)
- Structural Function = Non-Load-Bearing Element
 - Accessible = True
 - Layer = A-_ANOT---_A-
- 3 Place the necessary symbol to the lifts which are to be marked as accessible.



4 Open the **Schedules/Element/A | Lifts** schedule in the **Project Map** to check the results and make the necessary changes as needed.

LIFTS							
		Car Inner Dimensions					
Accessible	ID	Clear Opening Width			Quantity	Remarks	
	AL - 001	900	2,000	1,500	1		
					1		
	L - 001	900	2,000	1,500	1		
	L - 002	900	2,000	1,500	1		
					2		
					3		




Toilets and Toilet Compartments

Accessible toilets have to be set according to the accessibility code and will be highlighted on plans. For actual requirements please refer to the relevant codes.

Note: There is a difference between individual toilets and toilet compartments. If you want to add compartments to your model you may decide whether to use the Commercial Bathroom Stall objects with or without the stall separators or built walls with single WC elements. Mixing the different types is not recommended.

1 Use the **Object** Favorites under the **BIM SUBMISSION/Toilets**, **Basins**, **Urinals** folder.



Note: A default Cluster ID property is stored with the Favorites, therefore it has to be changed manually.

- 2 **Double-click the preview** to activate the Object tool and apply the Favorite settings. Check the following **Classification and Properties** settings:
 - Element Classification = MEP Element
 - ID = (according to company naming standards)
 - Structural Function = Non-Load-Bearing Element

- Accessible = False or True (as needed)
- Layer = A-_SANI----_E-
- 3 Place the necessary toilets.

Add the 2D symbol for accessibility to mark the accessible and ambulant disabled toilets on plans as well.

1 Use the Object Favorites Ambulant Disabled 3D Text and/or WC Clearance (d=1000) under the BIM SUBMISSION/Accessibility Symbols/Objects folder.



- 2 **Double-click the preview** to activate the Object tool and apply the Favorite settings. Check the following Classification and Properties settings:
 - Element Classification = Building Element Proxy
 - ID = (according to company naming standards)
 - Structural Function = Non-Load-Bearing Element
 - Accessible = True
 - Layer = A-_ANOT----_A-
- 3 Place the necessary symbol next to the toilets which are to be marked accessible to highlight the function and their clearances.

Note: The 2D linework of the compartment toilets is limited. Grab bars, toilet paper dispensers, etc. need to be added manually.

4 There are separate Schedules for single toilets and compartment toilets. They should not be mixed.

Single Toilets: Open the Schedules/Element/Toilets schedule in the Project Map to check the results and make the necessary changes as needed.

TOILETS						
Home Story	Accessible	Туре	Quantity	Remarks		
1st STOREY,	Cluster 01					
		Urinal 20	3			
		WC 20	6			
	\square	Urinal 20	1			
	\square	WC Disabled 20	1			
			11			
1st STOREY,	Cluster 02					
		Urinal 20	2			
		WC 20	4			
	\square	Urinal 20	1			
	\square	WC Disabled 20	1			
			8			
2nd STOREY,	Cluster 03					
		Squatting Toilet 20	4			
		Urinal 20	3			
		WC 20	2			
		Urinal 20	1			
	\square	WC Disabled 20	1			
			11			
			30			

Compartment Toilets: Open the Schedules/Element/Toilets (Compartments) schedule in the Project Map to check the results and make the necessary changes as needed.

TOILETS (Compartments)					
Home Story	Accessible	Number of Stalls (toilets)	Remarks		
1st STOREY,	Cluster 01	·			
		3			
		1			
		4			
2nd STOREY	, Cluster 02	·			
		3			
		1			
		4			
		8			

Accessibility Objects

The linked *GSSG ARCH Library.lcf* contains objects that can be used during the submission phase, such as the **Detectable Warning Surface** and **PWD Area** objects and the **Parking Lot Symbol** objects (2D only).

n GSSG ARCH Library.lcf	~		È 📰	D,
✓ 💼 GSSG ARCH Library.lcf				^
🗸 🛅 SG ARCH Library	AD			
Accessibility Objects				
	Ambulant Disabled 3D Text	Clearance Box.gsm	Detectable Warning Surface	
			F	
	ě.	rìiliùa	i & i	
	Parking Lot Symbol (Accessi	Parking Lot Symbol (Family)	PWD Area.gsm	
			R	
	Ġ.	II	GL	
	Seating	Seating	Symbol of	
	(Accessible).gsm	(Single).gsm	Access.gsm	
		R	\mathbb{R}	~
	Name:	Accessibility Objects		
	Placed objects:			0
	Placed instances:			0
	Library parts used in	attributes:		0
				_
	BBR	RF: X		(i)
 All library parts were loaded successfully 				
 All library parts were loaded successfully 				

When using these objects, make sure that their settings (for example Accessible: True/False) will allow them to be highlighted in the relevant views and schedules. Refer to object settings of similar objects in this chapter.

The additional 2D parking lot symbols are only to be used if the built-in representation of the parking lots does not suffice. However, note, that the submission process only requires the function and accessibility of the parking lots and not their final appearance, therefore the default ones can be replaced later for tendering, construction, etc. phases.

Note: The final parking lot schedule has to indicate the number of all parking lots and the breakdown in between accessible and regular spaces. If needed, change the schedule criterion accordingly when using these additional elements.

SCHEDULES

The officers will use the Schedules to perform manual code-checking to see whether the model is built according to the regulations and will comment as necessary. The following sections will introduce the template schedules and present the necessary settings for the related elements.


To access, go to the SCHEDULES folder in the View Map.

Accessible (Audience) Seating

This schedule lists the total number of auditorium-type seating and the number of accessible seating and sorts them based on accessibility per stories/rooms. For actual requirements please refer to the relevant codes.

Note: The schedule does not list the *Audience Seating 26* object in the *Archicad Library 26*.

1 Use the Object Favorite Seating or Seating (Accessible) under the BIM SUBMISSION/Accessibility Symbols/Objects folder.




- 2 **Double-click the preview** to activate the Object tool and apply the Favorite settings. Check the following **Classification and Properties** settings:
 - Element Classification = Furniture or Building Element Proxy (as needed)
 - ID = (according to company naming standards)
 - Structural Function = Non-Load-Bearing Element
 - Accessible = False or True (as needed)
 - Layer = A-_FURT----_E-
- 3 Place the necessary objects.
- 4 Open the SCHEDULES/BCA_BP_AUDIENCE SEATING schedule to check the results and make the necessary changes as needed.

ACCESSIBLE SEATING							
Home Story	Accessible	ID	Remarks				
1st STOREY,	Auditorium						
		REGSEAT					
		121					
	\square	ACCSEAT					
		5					
		126					



Hearing Enhancement Systems

This schedule lists the number of Hearing Enhancement Systems (HES) symbols per rooms. For actual requirements please refer to the relevant codes.Use the **Object** Favorite **HES** under the **BIM SUBMISSION/Accessibility Symbols/Objects** folder.




1 **Double-click the preview** to activate the Object tool and apply the Favorite settings.

Check the following Classification and Properties settings:

- Element Classification = Building Element Proxy
- ID = (according to company naming standards)
- Structural Function = Non-Load-Bearing Element
- Accessible = True
- Layer = A-_ANOT----_A-
- 2 Place the necessary objects.
- 3 Open the SCHEDULES/BCA_BP_HEARING ENHANCEMENT SYSTEMS schedule to check the results and make the necessary changes as needed.

HEARING ENHANCEMENT SYSTEMS						
Home Story	Room	Quantity	Remarks			
1st STOREY			I			
	Auditorium	1				
		1				
2nd STOREY						
	Training Room 1	1				
	Training Room 2	1				
		2				
		3				



Parking Lots

This schedule lists the number of parking spaces and sorts them based on accessibility. For actual requirements please refer to the relevant codes.

Note: The schedule only lists the variants of the *Parking Place 26* object of the default *Archicad Library 26*.

1 Use the **Object** Favorites under the **BIM SUBMISSION/Parking Lots** folder.

	tled - Archicad 27			
26500015	dit View Design Documen	t Options Teamwork Wind	100000000000000000000000000000000000000	
5		< • 💩 • # • 👁 🕴		
Main:	6	yen	Elem	
Default	Q Search Favorites		@•,	
-	Parking Lots	~	E	
R				
	le ta			
Design	1 - A. S. A.	/ C4		
0	Accessible (Double - 2x	Accessible (Single - 3600x500	0)	
	3600x5000)	, and the congret of the second of		
Ð				
A	1. 0. 0. 0	11.		
A	1. M. M.	- 1. J.		
B				
F	Accessible (Triple - 3x	Car (Double - 2x 2500/5000)		
	3600/5000)			
田				
Ð	111			
田	1 1. /			
B				
	Car (Double Minimal - 2x	Car (Multiple - 10x 2500/5000	0)	
四	2400/5000)			
B				
Q	Carlo and	/ /		
		1. /		
R				
Viewpoi		Car (Single - 2500/5000)		
Docume Enter A			1	

- 2 **Double-click the preview** to activate the Object tool and apply the Favorite settings. Check the following **Classification and Properties** settings:
 - Element Classification = Building Element Proxy
 - ID = (according to company naming standards)
 - Structural Function = Non-Load-Bearing Element
 - Accessible = False or True (as needed)
 - Layer = **A**-_**CPRK**----_**E**-
- 3 Place the necessary objects.
- 4 Open the SCHEDULES/BCA_BP_PARKING LOTS schedule to check the results and make the necessary changes as needed.
- 5 Add remarks to the Accessible/Family Car Park Spaces to confirm that the required total width is provided.


PARKING LOTS							
Home Story	Accessible/Family Car Parking Lot	ID	Minimal Width	Length	Number of Parking Spaces	Remarks	
1st STOREY	I		1	1	-1	1	
		CPRK - 001	2,500	5,000	38		
		CPRK - 002	2,500	5,000	38		
		CPRK - 003	2,500	5,000	38		
		CPRK - 004	2,500	5,000	38		
		CPRK - 005	2,500	5,000	38		
		CPRK - 006	2,500	5,000	38		
					228		
		A-CPRK - 001	2,500	5,000	2	additional width of 1100 provided	
		A-CPRK - 002	2,500	5,000	2	additional width of 1100 provided	
					4		
					232		



Accessible/Elderly Friendly Rooms (Hospitality Projects Only)

This schedule lists the number of Accessible Rooms in hotels, dormitories, guesthouses and other hospitality buildings. For actual requirements please refer to the relevant codes.

Note: All Accessible Rooms and Elderly Friendly Rooms are Accessible spaces; other room type may or may not be considered Accessibly spaces.



1 Use the Zone Favorite Accessible/Elderly Friendly Room (Hospitality only) NET.

2 **Double-click the preview** to activate the Zone tool and apply the Favorite settings.

Check the following Classification and Properties settings: - Element Classification = Space

- Accessible = True
- Accessible Room/Elderly Friendly = True (only one applies)
- Layer = A-_AREAGFAA_A-
- 3 Place the necessary zones.
- 4 Open the SCHEDULES/BCA_BP_ROOMS (Accessible) and (Elderly Friendly) schedule to check the results and make the necessary changes as needed.

ACCESSIBLE ROOMS (Hotels, guesthouses, dormitories, etc.)						
Home Story	Room Name	Room No.	Quantity	Remarks		
1st STORE	(1	1 1			
	Room	101	1			
	Room	102	1			
	Room	103	1			
			3			
2nd STORE	Y					
	Room	201	1			
	Room	202	1			
	Room	203	1			
			3			
3rd STORE	Y					
	Room	301	1			
	Room	302	1			
	Room	303	1			
			3			
			9			

ELDERLY FRIENDLY ROOMS (Hotels, guesthouses, dormitories, etc.)							
Home Story	Room Name	Room No.	Quantity	Remarks			
2nd STOREY	,	1					
	Room	201	1				
	Room	202	1				
	Room	203	1				
			3				

All Rooms

This schedule lists all rooms with their ventilation types, accessibility options and areas. The main purpose of this list is to enable easy data handling as described in the <u>ACCESSIBILITY &</u> <u>VENTILATION</u> section of this document.

- 1 Open the SCHEDULES/BCA_BP_ROOMS (All) schedule to check the results and make the necessary changes as needed.
- 2 Click into the Mode of Ventilation cells and use the arrow to open the option list or check/uncheck the checkboxes.

Mode of Ventilation	Area	Accessible (space)	Hotels, guesthouses, dormitories, etc.		Quantity
	Area		Accessible Room	Elderly Friendly Room	Quantity

ROOMS	(All	Types)
-------	------	--------

Mechanical 🔹 🕨	Natural			1
Mechanical	Mechanical			1
Mechanical and Air-Conditioned	Natural and Air-Co			1
Mechanical and Air-Conditioned	Undefined	r-Conditioned		1
Mechanical and Air-Conditioned	02.70			1
Mechanical and Air-Conditioned	104.97	\boxtimes		1
Mechanical and Air-Conditioned	15.06			1
Mechanical and Air-Conditioned	15.07			1
Mechanical and Air-Conditioned	16.63			1
Natural and Air-Conditioned	24.64	\boxtimes		1
Natural and Air-Conditioned	14.46	\boxtimes	\boxtimes	1
Natural and Air-Conditioned	30.98	\boxtimes		1
	605.12 m ²			12

	<u></u>		 	
Natural and Air-Conditioned	24.64	\boxtimes	\boxtimes	1
Natural and Air-Conditioned	14.46	$\mathbf{\nabla}$	\checkmark	1
Natural and Air-Conditioned	30.98	\boxtimes	\boxtimes	1
Mechanical	30.81			1
Mechanical	30.81			1
	131.70 m ²			5

Stairs

This schedule lists all Stairs elements. The main purpose of this list is to check the tread sizes and number of steps per flights. For actual requirements please refer to the relevant codes.

1 Open the SCHEDULES/BCA_BP_STAIRCASE schedule to check the details of the stairs you created and make the necessary changes as needed (might not be possible within the schedule).

								BCA_BP_S	TARCASES					
D	Home Story	0.0	Detectable Warning	Number of	Tread Dept	hs (byrule)) Riser Heights (by rule)		Railings					Remarks
D	Home Story	Clanuty	Surfaces	Risers per Flights	min.	mex.	min.	mex.	Distance Between Railing Posts	Distance from Landing/Right	Height of Curb (perpendicularly)	Height of Ourb (vertically)	Height of Railing	Hemarks
TAIR - 0	01					-								
	1st STOREY	1		20	250	350	150	200	100	150	115	115	100	
TAIR - 0	02													
	1st STOREY	1	Ø	20	250	350	150	200	100	150	115	115	100	
TAIR - 0	03												•	
	1st STOREY	4		0 ; 13	250	350	150	200	100	150	115	115	100	
		6												

2 Add Comments/Remarks as needed.

Stairs that were created by other tools, will NOT be listed therefore need additional comments/remarks in the remark field stating:

- Tread sizes (riser and run)
- Railing height (total, including plinths/curbs)
- Number of steps per flight
- Flight widths


Using non-stair modeling tools is not recommended, but if used always set the Element Classification to Stair and adjust the Schedule criteria to include them.

The remarks can also be used to refer to Railings that will be used with the Stair.

Shelters

These schedules list all household and staircase shelters. Shelters use the Zone tool for the area calculation as ordinary spaces, the setbacks are represented by Morphs. The list needs manual filling of properties of the above-mentioned elements as follows.

Note: The shelter setbacks are using one common layer that is only shown on the FSSD layer combination. Any additional layers that might be needed for shelter (setbacks) must be incorporated into the FSSD layer combination.



2 **Double-click the preview to activate the** Zone tool and apply the Favorite settings.

Check the following **Zone** settings:

- Zone Category = CDHS Household Shelter/CDSS Storey Shelter/CDSSS
 Staircase Storey Shelter (according to the type of actual shelter)
- Element Classification = Space
- Property Group = **ARCH** | **SHELTERS** the content of this group is only to be used for shelter zones
 - Dwelling Unit Type: according to the type of unit (create more property value options under **Options/Property Manager...** as needed
 - GFA of Unit: input the total GFA of the unit in which the shelter is located


- Shelter Type (not for Staircase Storey Shelter): HA/HB/SA/SB according to the position of the shelter, this value can be set in the schedules as well
- No. of Square Units: expression-based calculation, according to the code of practice
- Required Internal Area: expression-based calculation, according to the code of practice
- Required Internal Volume: expression-based calculation, according to the code of practice
- Layer = according to the GFA/NonGFA type of actual shelter
- 3 Place the necessary Zones.
- 4 From the **Project Map**, open the **Element/Shelters** | ... schedules to check the results and make the necessary changes as needed.
- 5 Click into the Schedule cells to change details as needed.

DATA OF HOUSEHOLD SHELTERS							
Dwelling Unit Type	GFA of Unit	No. of HS	Internal Area	No. of Square Units	Internal Volume	Shelter Type	
Type 1	45.30	2	9.72	27	31.14	HA	
Туре 2	60.20	2	14.34	39	45.88	HA	
Туре 3	87.40	2	9.72	27	31.14	HA	

DATA OF STOREY SHELTERS									
Home Sterry	Dwelling Unit Type	CEA of Unit	Quantity	Internal Area of SS		Internal Volume of SS			
Home Story	Dwelling Unit Type	GFA of Unit	Quantity	Required	Provided	Required	Provided	Shelter Type	
1st STOREY								•	
	Undefined	132.50	1	3.00	14.95	9.00	47.86	HA	
2nd STOREY									
	Undefined	132.50	1	3.00	14.95	9.00	47.86	HA	
			2						
	1				1	1	1	1	

Find more information on the Expressions in Properties on the Archicad 27 Help here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F045_PropertiesC

lassifications%2F045_PropertiesClassifications-9.htm



Examples of a Floor Plan and 3D view showing shelters:

Courtesy of P&T Consultants Pte Ltd.

AREA TABULATION

GFA

Schedule URA_LV_ SUM OF GROSS FLOOR AREA (GFA) (New) can be viewed under the SCHEDULES folder of the View Map.

- 1 Open a Floor Plan viewpoint from the Navigator.
- 2 Activate the **Zone tool** and open its settings and choose the appropriate **Favorite** (any of the GFA Spaces/Non-GFA Spaces).
- 3 Set Zone Category and insert a Zone Name. Always set the Zone Top according to the actual story heights, consider top offsets when linked to a story above. The top of the Zones should always touch the bottom surface of the element(s) above. Subfloor Thickness also has to comply with the actual composite settings (finishes) of the bottom construction.

\$ ·	Default
Top Link:	Number:
1. 2ND STOREY (Home + 1) ~	<room number=""></room>
-200	Name: <zone name=""> Category: GFA GFA Zone</zone>
Home Story:	Zone Polygon:
0. 1ST STOREY (Current)	() Net
to Project Zero	Subfloor Thickness:

4 In the Classification and Properties panel, change the Mode of Ventilation property to define the type of ventilation. This will be displayed in the Zone Stamp. Also fill the BlockNo (Pset_SpaceCommon) IFC property at the bottom of the list as necessary.

Check the appearance of the Zone Stamp under **Zone Settings**: Zone Name, Measured Area and Classifications and Properties should be displayed.

Zone Default Settings	?	×
		Default
▶ 🖗 NAME AND POSITIONING		
▶ [, ¹] FLOOR PLAN		
V ZONE STAMP		
▶ 1Å STAMP TEXT STYLE		
▼ XIII SETTINGS		
Content		•
1. Zone Name V - +		
2. Measured Area ~ - +		
3. Classificationd Properties V - +		

5 Set the Layer to A-_AREAGFAA_A-_.GFA and create the Zone polygon of the floor plan. Click with the hammer icon to place the Zone Stamp.

Note: To turn on/off the display of the Ventilation Type parameter (or other properties from the Tags and Categories panel) in the Zone Settings dialog, go to Settings panel, Classification and Properties page/1. Row and change the value to None or select one from the available parameters.

To turn off the display of all metadata in general go to the Zone Settings panel/Content page and click the (-) button besides the Classification and Properties row.

- 6 Open the URA_LV_ SUM OF GROSS FLOOR AREA (GFA) (New) schedule.
- 7 To configure the contents of this and other Schedules, click the Scheme Settings... button at the top right.

STRATA

Schedule URA-_LV_ STRATA can be viewed under the SCHEDULES folder of the View Map.

- 1 Open a Floor Plan viewpoint from the Navigator.
- 2 Activate the **Zone tool** and open its settings and choose the Favorite **UNIT**.
- 3 Set Zone Category and insert a Zone Name. Always set the Zone Top according to the actual story heights, consider top offsets when linked to a story above. The top of the Zones should always touch the bottom surface of the element(s) above. Subfloor Thickness also has to comply with the actual composite settings (finishes) of the bottom construction.

Zone Selection Settings ? × Selected: 1 Editable: 1 Selected: 1 Editable: 1 Selected:		
NAME AND POSITIONING Top Link: 1. 2ND STOREY (Home + 1) -200 -200 -200 Caregory: Category: Cone Polygon: Image: Descent Constant Category: Image: Descent C	Zone Selection Settings	? ×
Top Link: 1. 2ND STOREY (Home + 1) I. 2ND STOREY (Home + 1) I. 2ND STOREY (Home + 1) Number:	な・	Selected: 1 Editable: 1
1. 2ND STOREY (Home + 1) Image: Content number > Name: Content number > Image: Content number > Name: Category: Category: Category: Category: Category: Category: Category: Category: Category: Content number > Image: Content number > Image: Category: Ca	▼ P NAME AND POSITIONING	
-200 -200 Scone name> Category: 3200 0 Category: GFA GFA GFA Zone Zone Polygon: 0 Home Story: 0. 1ST STOREY (Current) to Project Zero Subfloor Thickness:	Top Link:	Number:
-200 -200 -200 Category: GFA GFA Zone Zone Polygon: O Net O Net O Net Subfloor Thickness:	1. 2ND STOREY (Home + 1)	<room number=""></room>
Category: GFA GFA Zone Category: GFA GFA Zone Zone Polygon: O Net to Project Zero Subfloor Thickness:		Name:
3200 GFA GFA Zone 0 Cone Polygon: 0 Cone Polygon: 0 Home Story: 0.1ST STOREY (Current) to Project Zero Subfloor Thickness:	-200	<zone name=""></zone>
Image: Construction of the project Zero Image: Construction of the project Zero Image: Construction of the project Zero Image: Construction of the project Zero		Category:
Home Story: 0. 1ST STOREY (Current) to Project Zero	3200	GFA GFA Zone
Home Story: 0. 1ST STOREY (Current) to Project Zero		Zone Polygon:
0. 1ST STOREY (Current)		Gross
to Project Zero		Net
100 100	to Project Zero 🕨	Subfloor Thickness:
	100	100

- 4 Place the necessary Zones.
- 5 Open the SCHEDULES/URA_LV_STRATA schedule to check the results and make the necessary changes if needed.

STRATA (Units)							
Home Story	Name	Area	Quantity				
1st STOREY							
	Unit A	137.75	1				
		137.75 m ²	1				
	Unit B	64.34	1				
		64.34 m ²	1				
2nd STOREY							
	Unit A	137.75	1				
		137.75 m ²	1				
	Unit B	64.34	1				
		64.34 m ²	1				
		404.18 m ²	4				

SGFA

These Schedules are found in the SCHEDULES folders of the View Map.

- BCA_LV_ STATISTICAL GROSS FLOOR AREA (SGFA) 2
- BCA_LV_ STATISTICAL GROSS FLOOR AREA (SGFA) GENERAL
- BCA_LV_ STATISTICAL GROSS FLOOR AREA (SGFA) SPECIFIED
- BCA_LV_SUM OF AREAS NOT INCL IN GFA COMPUTATION

To generate the SGFA table for areas NOT calculated as GFA automatically:

- 1 Activate the Zone tool and open its settings and choose the appropriate Zone Category and insert a Zone Name.
- 2 Set the building type of the Zone under Classification and Properties/ARCH | SGFA/Building Type (SGFA), the other Properties in this group are expression-based.

		ARCH SGFA		^
G	⊇ ▶	Building Type (SGFA)	General 💽	
9	ē	Position to Sub-Level	<expression></expression>	
5	ē	General Area	<expression></expression>	
G	ē	Specified Area	<expression></expression>	
G	ē	Elevation Calculation	<expression></expression>	
		ARCH ZONES		
C	3	Purpose of Zone	Hospitality	
G	<u>.</u>	Hotlink Master ID and Zone N	<expression></expression>	
G	<u>.</u>	Window Surface Area/Room A	<expression></expression>	
G	ē	Transparent Window Surface R	. 100.00	0
-	-			~

- 3 Set the Layer to A-_AREAGFAD_A-.NonGFA if the Zone is a Non-GFA Zone and create the Zone polygon on the floor plan.
- 4 Open the respective schedules under the SCHEDULES folder of the View Map.
- 5 To view the final SGFA plans, open views from the BCA/BP/2D PLANS/SGFA PLANS folder in the View Map.

Note: Always check the Scheme Settings of each schedule before using and make sure you understand its Criterion and Fields.

COVER PAGE

Though the Native BIM Submission is mainly based on views, Layouts are still required for submission. The Layout Book contains a COVER PAGE (which contains all the required project information), and some Sample layouts if needed.

1 Open the COVER PAGE layout from the Layout Book.


× +	

- 2 Fill the necessary project information using **Project Info**, access dialog from the context menu of the Layout Book or go to File/Info.
- 3 Use the revisions according to the project status to make use of the **Revision History Object** or remove the object on the A1 LANDSCAPE master layout and use the free space for your convenience.

Find more information about Revision Management on the Archicad 27 Help here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F070_Documenta tion%2F070_Documentation-97.htm%23XREF_24975_Revision_Management 4 Make sure that the View List, Schedule List and Drawing List are clearly visible. If necessary, change the cell sizes of the schedules in the View Map/COVER PAGE folder. If line breaks occur at wrong positions, modify the drawings using the Restructure Table command of the Pet palette. Click the bottom corners to activate it.




- 5 Fill the **Custom Fields** in the title block (remove the highlight boxes first) as needed.
- 6 Replace the Endorsements on the Master Layouts. Go back to the Project Map/Worksheets/1 ENDORSEMENTS and look for the necessary textbox. Copy and paste it to the COVER PAGE master layout.



A&A WORKS (RENOVATION)

By default, all elements are defined as *New*. Renovation Filter colors are based on the CP83 color coding.

Use the Renovation palette (find in menu **Window/Palettes/Renovation**) to change the default renovation status of elements or change the current renovation status of specific elements, which are selected.




To change all Renovation Statuses of all elements (for example change all New elements to *Existing* after finishing a phase) use the Document/Renovation/Reset Renovation Status... dialog.

Reset Renovation Status	?	' ×
pecify what happens with Elements current	y in the project:	
xisting Elements:	摆 Keep Status as is	~
o Be Demolished Elements:	X Delete	~
lew Elements:	E Set to Existing	~
Show All Elements on All Relevant Filters		
This will affect ALL editable Elements	in ALL Viewpoints!	
	Cancel	OK

Find more information about the **Renovation** feature on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F050_ViewsVB%2F05 0_ViewsVB-123.htm For additional Renovation filtering options:

- 1 Go to Document/Renovation/Renovation Filter Options....
- 2 Under Filter Settings, filtering options can be changed per filter. To edit the graphical appearance of elements with different statuses use the **Graphic Override Rules...** button at the bottom right.
- 3 Select the status at the top left to override to modify the 2D/3D representations under Override Style.



COLLISION DETECTION (OPTIONAL)

Collision detection is optional and can be carried out in between accessibility elements and regular building elements to ensure access and clearances. This is completely voluntarily and will not be checked by the officers, however it can increase the quality of the BIM project.

- 1 Launch the Design/Model Check/Collision Detection... dialog.
- 2 **Define the two groups** you wish to check for collisions between. Pre-set Find & Select Criteria Sets can be used for this purpose. Then click **Check**.
- 3 The **Model Check Report** palette will open indicating all found collisions. If there are too many, it may be worth to delete the entries and run the Collision Detection again after adjusting the criteria between each group to fine tune the check.

Model Check Report					×
	3 X			í	
Description	Element 1 ID	Element 2 ID	F	Creation Date	
Collision Detection	EXTWALL - 004	Duct-001		11/10/2021 4:40 pm	1
Collision Detection	EXTWALL - 001	Duct-006		11/10/2021 4:40 pm	
Collision Detection	EXTWALL - 002	Duct-002		11/10/2021 4:40 pm	
Collision Detection	EXTWALL - 001	Duct-004		11/10/2021 4:40 pm	
Collision Detection	EXTWALL - 002	Duct-005		11/10/2021 4:40 pm	1
Collision Detection	EXTWALL - 001	Duct-005		11/10/2021 4:40 pm	•

- 4 Review each entry by double clicking each to select and zoom to the elements in either the Floor Plan or 3D Window.
- 5 If the collision is a valid issue, either the issue should be fixed now or an Issue created, which can be managed by the team, by selecting the entry and clicking the icon with the Flag. If the collision is not a valid issue, then the Collision Detection criteria and/or visible Layers may need be adjusted to avoid the issue reappearing next time the Collision Detection is run.
- 6 If Collision entries have been added to the Issue Manager, a Flag icon will appear next to the entry in the report. To review all created Issues, go to Document/Issue Manager. From here, issues can be assigned to Teamwork members and managed.

Find more details on the Issue Manager on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F082_IssueHandling %2F082_IssueHandling-5.htm


MERGING THE TEMPLATE INTO AN EXISTING COMPANY TEMPLATE

The current version of the template contains most of the default settings that are shipped with the Archicad INT (International) version and the additional customizations to comply with the Native BIM Submission requirements. These template settings can be migrated into your existing company templates as follows.

Favorites

The template contains many pre-defined favorites. To migrate and transfer these:

- 1 Open the favorites palette from the menu Window/Palettes/Favorites from either the company template or submission template.
- 2 Click the cogwheel button at the top right and choose Import/Export....



Find more details on the Favorites Import/Export process on the Archicad 27 Help here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F020_Configuration %2F020_Configuration-60.htm

Attributes

Attributes include data such as Layers, Layer Combinations, Pens and Pen Sets, Lines, Fills, Composites, Complex Profiles, Surfaces and Building Materials.

- 1 Open Options/Element Attributes/Attribute Manager... of the company template file.
- 2 On the right side of the Attribute Manager you can import attributes from another file, by clicking the **Import** button.

,	ttributes	J	c 🗈 🗞		All Changes	
Layer Combinations	in Pr	oject		Tempo	orary	\rightarrow \rightarrow \times
# Name100 All Visible Shown Ed	itable	^	Duplicate	#	Name	~
101 BCA_BIM	Nuble		Delete			
102 BCA_BIM (no Access	sibility)		Purge			
103 CBPU			Reindex			
104 FSSD						
105 LTA 106 URA			Append >>			
106 ORA 107 CP83						
		~	By Index >>			~
Layers			By Name >>	Layers		
# 🛈 👁 🗗 🕅	ZZ Name		Include All	#	🛈 👁 🖪 🌠 Name	
✓ 1	Archicad Layer	^	Associated Layers			^
2	- Hidden					
✓ 3	- Drafting - General					
✓ 4 ✓ 5	 Accessibility Route.BCA_BP Clearance Boxes.BCA_BP 					
✓ 5 ✓ 6	- Clearance Boxes.BCA_BP					
7	- SEO - Operator					
8	- SEO - Operator (hidden)	~	Save as TXT			\sim

- 3 After the attributes are added to the Temporary list, select the different types of attributes using the selector tabs on the top of the dialog.
- 4 Select the attributes to import on the right, and choose **Append/By Index/By Name** to add them to the current project, the left list.
- 5 Click **OK**/**Apply**, a dialog will appear indicating number of changes being applied.

Find more information on the **Attribute Manager** on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F026_AttributeM anager%2F026_AttributeManager-1.htm

	6	Masonry	Block - F	520
<< Append	7 🧱	Concrete		▶ 510
<< By Index	8		- Structu	740
<< By Name	Associated Attri	butes		
Include All Associated	Туре	#	Name	
Attributes	🕢 Fill Type	7	Lightweight Concrete	1
	🖾 Fill Type	8	Grid 50x100	
	₿ Surface	5	Concrete - 04	

Note: Some attributes are connected to other attributes, what is referred to as 'associated attributes', (for example Building Materials are linked to Surfaces and Fills). When transferring, some attributes might get duplicated, if an already existing associated attribute was added via their dedicated attribute panel for example. Check the Changes panel, to review all attributes being created before committing to avoid unnecessary attributes being generated.

Attributes in the downloaded templates are arranged with Index number sequencing to comply with the one-model concept as well as detailed in the following table (STR and MEP attributes are not appearing in the current template for Architectural BIM submission, but in their respective templates).

	Archicad Defaults/General	ARCHI	STR	МЕР
Layers	1-89	101+ Landscape 201+	301+ Civil 401+	Electrical 501+ Mechanical 601+
Layer Combinations	1-3	101+	301+	501+
Pen Sets	1-5	-	301+	501+
Lines	1-26	-	301+	501+
Fills	1-161	201+	uses ARCHI	uses ARCHI
Composites	1-26	201+	-	-
Profiles	1-42	201+	-	-
Surfaces	1-230	-	-	-
Building Materials	1-60	201+	-	-
Zone Categories	1-12	201+	12	12
MEP Systems	1-6	1-6 (defaults)	1-6 (defaults)	1-33

Project Info

Open the File/Info/Project Info... dialog and fill out the relevant information for the project. To transfer between projects, use the Export and Import buttons

oject Info		?
PROJECT DETAILS		
Project Name	-> File/Info/Project Info	
Project Description		
Project ID		
Project Code		
Project Number	#Insert Project Ref. No.	
Project Status		
Keywords		
Notes		
Project Custom		
Accredited Checker	#Insert AC Name	
Surveyor	#Insert Surveyor Name	
Architect's Registration		
Architect's Address		
Mechanical Engineer		
Fire Safety Engineer		
Date of Issue	#Insert Date of Issue	
Template Created by	GRAPHISOFT Singapore, 2022	
Add Remove		-> ->
	Cancel	ОК

Views, Layouts and Master Layouts

Views, Layouts (and Layout Subsets) and Master Layouts cannot be exported directly.

However, by using the Organizer, and both project files open, you can show the contents of the second Project on the left, and use Drag/Drop to the current project on the right. Copied Drawings and Views will be linked from the second Project - which is a good method for splitting a project between Model and Documentation. Doing the same for Masters, will copy the Master content from one file to the other.

Alternatively, and maybe simpler, **copy** the contents of a Master Layouts from one file, and **paste** to the other file.

Find more information on Accessing Views/Layouts from another Archicad on the Graphisoft Help Center here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F030_Interaction%2F 030_Interaction-6.htm The View Map folders are generally using cloned folders. To create cloned content:

1 Use the Clone a Folder... button from the View Map.



2 Select the **Project Map folder** you want to clone, and review the ID, Name and General parameters, these will be used to generate the Views, and click **OK**, to automatically create views in the View Map that match the **Project** Map's content.

	TION		
			_
Choose Project			
	Info/Project Info		^
🖺 Storie	25		
C Sectio	ons		
🗋 Eleva	tions		
[00] [—
ID:	By viewpoint \sim		
Name:	By viewpoint ~	-> File/Info/Project Info	
Source:	-> File/Info/Project Info		
GENERAL			
DESIGN OP	TIONS		
▶ 2D/3D DOC	UMENTS		
▶ 3D ONLY			
▶ STRUCTUR			

3 In the Organizer (under Window/Palettes/Organizer), Drag the content of the cloned folders or the folders themselves from the View Map to the Layout Book. When dragging onto an existing Layouts, this will add those Views onto the Layout; when dragging between Layouts or onto a Subset, this will create a new Layout per View.

Find more information on **Cloning a folder**

on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F030_Interaction%2F 030_Interaction-7.htm

Publisher Sets

Publisher Sets have to be created in the company template file. After the Layout Book subsets are created, use the **Add Shortcut** >>> button in the Organizer to create auto-updated content within the Publisher Sets (same as the Clone function described earlier, notice the additional arrow symbol on the icon in the Publisher Set).

Organizer - Publisher	×
Search View Map	
✓ ☐ BCA	Search 'A Views (PDF)'
✓ □ BP	✓ 2 BCA
✓ 🗋 2D PLANS	~ р вр
FLOOR PLANS (Accessibility)	V 🔁 2D PLANS
BCA_FP_A_ ROOF STOREY	V 🚰 FLOOR PLANS (Accessibility)
BCA_FP_A_ 10TH STOREY	BCA_FP_A_ ROOF STOREY
BCA_FP_A_ 9TH STOREY	Por BCA_FP_A_ 10TH STOREY
BCA_FP_A_ 8TH STOREY	BCA_FP_A_ 9TH STOREY
BCA_FP_A_ 7TH STOREY	BCA_FP_A_ 8TH STOREY
BCA_FP_A_ 6TH STOREY	BCA_FP_A_ 7TH STOREY
Add Shortcut >>>	BCA_FP_A_ 6TH STOREY
View Properties	BCA_FP_A_ 5TH STOREY
	BCA_FP_A_4TH STOREY
₿ BCA_BIM	€⊕ ×
La 1:100	Properties
🖾 Entire Model	▼ Format
	- I Officia

The Publisher Set item names can also include Autotexts, such as codes, IDs, revision numbers, etc. Those custom fields that were created under the Layout Info Scheme can also be inserted.

- 1 Right-click on any item(s)/folder and choose Rename Items....
- 2 Add Autotexts from the Insert Autotext control, these can be combined with custom text as well.

🔼 Rename Item	S	?	\times		
O Automatic Na	Selected:	1			
Custom Name	2	Insert Autotext	•		
<sourceid> <sourceitemname></sourceitemname></sourceid>					
Preview:					
BCA_FP_A_ 5	TH STOREY				
	Cancel	Rename			

Find more details on **Renaming Items in the Publisher** on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F070_Documentation n%2F070_Documentation-117.htm



Renovation Filters

To transfer Renovation Filters between projects, do the following:

- 1 Open **Document/Renovation/Renovation Filter Options...** from the download template.
- 2 Select the A-A Works renovation filter on the left and click Export....

4 Change Plan 5 New Construction 6 Planned Status A Works A Works (Existing Only) A Works (New Only) A Works (New Only) A Works (To be Deleted only) FILTER SETTINGS Existing Elements: Elements to be Demolished: A New Elements: Hide Opening Dimension Marker Solid Cut Fill Do not Intersect Hide Opening Dimension Marker	 Duplicate Rename Delete Import Export 	Graphic Overri	J

3 From your company template file (or other project), use the **Import...** button in the same dialog, and select the previously Exported Renovation Filter.

Find more details on **Revision Management** in general on the Archicad 27 Help here: https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F070_Documentatio n%2F070_Documentation-97.htm

Model View Options

To transfer Model View Options between projects, do the following:


- 1 Open Document/Set Model View/Model View Options....
- 2 Select the **Model View Option** on the left and click the **Export** icon button.

Model View Options	1	? ×
Search Model View Combinations	Name:	Editable: 1
Simplified 3D	SUBMISSION	
C26 01 Site	CONSTRUCTION ELEMENT OPTIONS	
C26 02 Drafting	CURTAIN WALL OPTIONS	
C26 03 Building Plans		
226 04 Ceiling Plans	STAIR OPTIONS	
C26 Default	RAILING OPTIONS	
	DETAIL LEVEL OF STAIR AND RAILING SYMBOLS (ARCHICAD LIBRARY 27)	
JBMISSION (no Accessibility)	DETAIL LEVEL OF DOOR, WINDOW AND SKYLIGHT SYMBOLS (ARCHICAD LIBRARY 27)	
	MISCELLANEOUS SETTINGS FOR LIBRARY PARTS (ARCHICAD LIBRARY 27)	
	ZONE STAMP 03 CONTENT (GSSG)	
	ZONE STAMP 04 CONTENT (GSSG)	
	ZONE STAMP CONTENT (GSSG)	
New Delete	×	

3 From your company template file (or other project), use the **Import** icon button in the same dialog, and select the previously Exported Model View Option.

Graphic Override Combinations

- 1 Open Document/Graphic Overrides/Graphic Override Combinations....
- 2 Select the Graphic Override Combination on the left and click the Export icon button.



3 From your company template file (or other project), use the **Import** icon button in the same dialog, and select the previously Exported Graphic Override Combination.

Note: Graphic Override Rules cannot be exported/imported individually but will transfer with the Combination.

Find more information about **Graphic Overrides** on the Archicad 27 Help here:

https://help.graphisoft.com/AC/27/INT/index.htm?#t=_AC27_Help%2F050_ViewsVB%2F05 0 ViewsVB-137.htm

SUBMISSION REQUIREMENTS

Saving the files requires a specific naming format to define the following.

1 Make sure that the COVER PAGE layout is opened and moved to the beginning of the Tab Bar, followed by the Floor Plan of the project (which must be open to keep the file open in Archicad). This COVER PAGE has to be the first one that officers see when they open the file. All other tabs are to be closed.

[COVER PAGE]	BCA_FP_A_ 1st STOREY [0. 1st STOREY]

- 2 Use File/Save as... menu command and save you file in one of the different formats.
- BIM native file format and software version in a single file:

Archicad **.PLA**, version **27**, indicated in the file name, for example:

ABCDEF_A1_BLK01_A_A27_123456.pla

Note: PLA files include all library elements used in a project and make the file management easier for the submission, therefore it is highly recommended to use this format.

File naming conventions – as per the BCA General Requirements, indicating maximum number of characters per part:

Project ID (6) –	Author (2)	-	Model Part (6)	_	Submission Version (1)	Softw Versi (3	ion	_		Use	er D (6	efir 5)	ned	
ABCDEF	Δ 1	R			А	ΔΣ	7		1	2	z	Л	5	6

Before submitting the file make sure all necessary views are set correctly and show the relevant information.

Final Check

Before submitting the file, make sure all necessary views are set correctly and show the relevant information. Check the highlights using the **Graphic Override Combination** options BCA_BP | Accessibility and/or BCA_BP | Modes of Ventilation.

Make sure that all external references (2D drawings) are stored within the project file, to ensure that the checking officers will see the same content as the QP.

- 1 Select the linked drawings (this can be done through the **Drawing Manager**) and open their settings.
- 2 Check the Store Drawing in the Project file checkbox for each drawing.

Drawing Selectio	n Settings	? ×
☆・		Selected: 1 Editable: 1
	TION	
Drawing ID:	By View ID	✓ BCA_FP_A_
	🗹 Include Drawing in ID sequ	ience
Drawing Name:	By View: Name only	V 1ST STOREY
Source File:	▶ Internal	
Archicad view:	\-> File/Info/Project Info\BCA	\BP\2DAccessibility)\BCA_FP_A_ 1ST STOREY
Update Type:	Auto	Last updated: 20/11/2022 6:49 pm
	OManual	Update Status: OK
Store Drawing in th	ne Project file	
Note: Use the Drawing	g Manager Palette to modify the sou	rce and update this Drawing.

File Formats

Based on the BIM e-Submission General Requirements (v1.1, 2017), the deliverables must be submitted in the following formats. Before submission, always check the requirements as they may change from what are outlined in this document.

- URA and BCA:
 - Native file format: .PLA
 - Lightweight file format: .PDF and/or .BIMX
 - SCDF, NEA, PUB, NParks, LTA, HDB, JTC:
 - Lightweight files format: .PDF and/or .BIMX

All drawing views (plans, elevations, sections, layout views or sheets) must be compiled into a single file with the 3D model.

ACKNOWLEDGEMENT

Revision of the current template and guide done by GRAPHISOFT Singapore, with the help and input from our users.

For any queries please contact:

